# Elevating Excellence. Exciting future for Le Pelley.

**Granite Le Pelley has rebranded as 'Le Pelley' in Jersey. A name that is recognised for their history and heritage whilst setting them free to embrace the future. The new brand reflects their commitment to delivering excellence to their customers and clients, their ability and intention to work with materials beyond granite.**

Their comprehensive services cover everything from design consultation to installation, ongoing maintenance and restoration. They collaborate closely with architects and interior designers to craft bespoke designs that reflect their clients' unique vision for residential and commercial projects.

Fundamentally, what truly distinguishes them is their design facility and their ability to combine their design and technical skills to find solutions to very intricate projects. This encompasses everything from kitchen flooring and vanity units and book-ended marble tiling in bathrooms of high-net-worth residential homes to the external cladding on developments such as the Premier Inn at Charing Cross and the new Horizon apartments at the Waterfront (Jersey). Their skilled work extends to areas such as Rainscreen Cladding and Traditional Stone Masonry.

With an impressive portfolio of heritage projects, Le Pelley showcases their expertise through the restoration of NatWest bank in the heart of St Helier, a historically rich area of the main town. Dating back to 1873, this impressive building posed challenges that Le Pelley skilfully overcame.

Facing the task of repointing granite walls, damaged Portland limestone and treating rusty rebar in concrete elements, Le Pelley approached the project with determination, recognising the structural concerns and damage to the building. This started with a low pressure steam clean of the granite, limestone and concrete surface using DoFF and TORC systems, followed by a thorough survey, taking into account the building's 150 years old history and the varying materials used in its construction, including precast elements.

Le Pelley addressed the building's diverse materials by selectively replacing only the most deteriorated element of the facade. This meticulous process tailored the approach to each building section, emphasising the importance of preserving original materials. Le Pelley adhered to a philosophy that viable elements, even with a limited lifespan, warranted conservation. The team prioritised strengthening and restoring, removing risky elements while preserving the building's historical integrity.

The 4 months long project demanded different techniques in different areas, with silicone moulds taken from the best-preserved features. These moulds were sent to Albion Stone in Portland, serving as templates for skilled craftsmen to carve intricate pieces by hand.

Their commitment to understanding the building's faults and the client's trust in them allowed for a sympathetic restoration, respecting the character of the limestone and reconstituted elements. A dedicated team committed to restoring history with precision, expertise and enthusiasm for preserving architectural heritage.

Technically, everything Le Pelley does is very challenging. Their exceptional team and state-of-the-art technologies, enable them to manage complex structural engineering projects and stone solutions in Jersey.

For more information about our services, please contact Le Pelley on **01534 832488** or email **pmaurice@lepelley.je**

**www.lepelley.je**

NATURAL STONE | FACADES | INTERIORS | LANDSCAPES

Le Pelley©

Crafting from imagination